

TIP Ref No.	CIP #	TFP #	Project Name	Project Description	Unsecured 2023-2028 Funding	Local* Funding	Other** Funding	Total Funding	Total Cost	Notes
<b>Projects Included in the Adopted 2023-2029 Capital Investment Program (CIP) Plan - Full or Partial Funding Secured</b>										
-	M-19		98th Avenue SE and SE 11th Street Slope Stabilization Project	This project will design and construct a soldier pile wall at the southwest corner of the 98th Avenue SE (97th Place SE) and SE 11th Street intersection to prevent further moving of the slope and prevent undermining the roadway. The project will make stormwater system improvements by collecting additional of water from slopes on the east side of 98th Avenue SE and 97th Place SE to prevent future saturation of the slopes. The project also included the replacement of an existing water main; pavement overlay and mitigation for slope impacts.		706	1,353	2,059	2,059	Project complete in 2025
-	R-191	TFP-265	124th Avenue NE/Ichigo Way (NE 18th St) to Northup Way	This project will complete design, property acquisition and construct improvements to 124th Avenue NE between Ichigo Way (NE 18th Street) and Northup Way, which will include travel lanes, turn lanes, street lighting, traffic signals, sidewalk facilities, culvert replacement, wetland and critical area mitigation, landscaping, underground utilities, urban design treatments, and provisions for gateways. This project also provides funding to complete design, property acquisition and construction of a multipurpose pathway on the west side between NE 16th Street and Ichigo Way and replaces existing City of Seattle transmission towers with mono-tube towers. (This project contains TIFIA funding)		1,539	39,601	41,140	41,140	Project complete in 2025
-	R-200	TFP-277	NE 8th Street/140th Avenue NE	This project will convert the existing southbound right turn lane to a through-right lane and will widen the south leg to create space for an approximately 250 foot receiving lane that will merge back into the existing through lane.		1,600		1,600	1,600	Project deleted; looking at alternate solutions.
-	WB-76	TFP-283	123rd Avenue SE/SE 60th Street to SE 65th Place	This project will complete the missing segments of sidewalk along the west side of 123rd Avenue SE from SE 60th Street to SE 65th Place.		1,700		1,700	1,700	Project to be complete in 2024
<b>Unfunded Projects included in the Preliminary 2022-2033 Transportation Facilities Plan</b>										
<b>Other unfunded local projects identified and scoped by completed Alternative Analyses and Planning or Pre-design Studies</b>										
-			142nd Place SE/SE 32nd Street	Add a southbound right turn lane.	810			0	810	Project components now part of R-201 Bellevue College Connection
<b>Regional or Outside Agency-Led Projects in which the City May Choose to Participate Financially</b>										