# Bellevue Way SE HOV – 112<sup>th</sup> Ave SE 'Y' to South Bellevue P&R Project Recommendation

April 24, 2017 – Study Session

#### **Presenters:**

Ron Kessack, Assistant Transportation Director Marina Arakelyan, Project Manager, City of Bellevue

#### Tonight's purpose:

- Present project scope recommendation
- Seek Council's approval of project recommendation


#### **Completed Activities: Project Definition**

- Developed several corridor options for roadway sections and project lengths
- Engaged community and other stakeholders
- Analyzed and refined project options based on input received
- ➤ Identified staff recommendation for a preferred option


#### **Public and Stakeholder Involvement:**

- City Council project update January 9, 2017
- ➤ Public/Online Open House January 19, 2017
- Chamber of Commerce February 14, 2017
- ➤ Bellevue Downtown Association Feb. 24, 2017
- Transportation Commission March 9, 2017
- Transportation Commission April 13, 2017

# SB HOV Project Roadway Width: Narrow Section vs. Wide Section




#### **SB HOV Project Length: Options Considered**




# SB HOV Project Length: Option 4 / Option 2 Cor

**Option 4 / Option 2 Comparison** 

	2030 No Build Baseline	Full Build Option 4: HOV through "Y" 112th Only	Full Build Option 2: HOV through "Y" BWSE & 112th	
Travel Times From Bellevue Way				
sov	7.5 min	7.9 min(+5%)	8.0 min(+7%)	
HOV	7.2 min	4.7 min(-35%)	4.4 min(-39%)	
Transit	6.7 min	4.7 min(-30%)	4.4 min(-34%)	
Travel Times From 112th Ave				
sov	9.9 min	10.1 min(+2%)	10.4 min(+5%)	
HOV	9.5 min	5.0 min(-47%)	5.6 min(-41%)	
Transit	10.6 min	6.0 min(-43%)	7.0 min(-34%)	
Peak Hour Volumes				
Total Vehicles	2,163	2,462(+12%)	2,492(+15%)	
Total People	3,876	4,490(+16%)	4,528(+17%)	
# HOV Vehicles	194	457(+236%)	463(+237%)	
# Transit Routes	20	20	20	
Conceptual Design, ROW and Construction Costs		\$31,000,000	\$35,000,000	



## **Project Recommendation**



#### **Next Activities – Early Design**

- Complete 30% design and environmental documentation Fall 2017
- Continue engaging with community and stakeholders
- Develop project phasing option(s) and recommendation
- Continue to develop project funding strategies
- Return to council for direction and approval on project phasing and advancing design –Winter 2018

## **Thank You!**


#### **Contact Information:**

Marina Arakelyan, project manager

Marakelyan@bellevuewa.gov;

ph. 425-452-4632

### SB HOV Project Roadway Width: Narrow Section – Preferred Option




- Equivalent traffic operations performance
- Less Critical Area Impacts
- Less Private Property Impacts
- For full build project length, narrow section is \$9 million less than wide section.

#### **Noise**

Condition	Noise Level	
Existing Noise Level	64 to 69 dB	
Without Project (w/ growth by 2030)	Add 0 to 1 dB	
With Project (No Noise Wall)	Change -2 to 2 dB	
With Project (10' to 20' Noise Wall)	Reduce by 2 to 7 dB	

#### **Noise Walls facts:**

- 10' to 20' would be in addition to 5' to 20' retaining walls needed
- Will block views
- Need to be continuous to be effective
- Cost approximately \$2M



#### January 19<sup>th</sup> Open House Feedback

- ▶ Preferred Length: Option 2 33% (10 of 30)
- $\rightarrow$  Acceptable Length: Option 4 70% (21 of 30)
- ➤ Preferred Width: Wider option 61% (22 of 36)
- > Construction Phasing:
  - No phased approach 56% (18 of 32)
  - If phased, option 4B (to Winters House) 60% (9 of 15)
- ➤ Aesthetics Design: Supported 75% (20 of 28)
- ➤ Noise Walls: Continue considering 63% (20 of 32)
- > Project Opposition: 10% (4 of 40)

Please note that respondents did not always answer all questions.