



Enatai Boathouse Roof Replacement Scope of Work

- Construction work includes removing the existing concrete roof deck. A new concrete roof deck will be poured.
- Damaged wood beams and under-roof wood planks will be replaced or repaired depending on their condition as determined by the Structural Engineer.
- Existing handrails will be replaced and painted to their original color.
- The sidewalk transition between the new roof deck and the existing sidewalk will be modified to comply with current ADA and building code regulations.